



Specifications :

- Concrete Minimum Compressive Strength - 4,000 psi @ 28 days
- Concrete Air Entrainment : 4% - 9%
- Type I, or Type I/II Cement
- Steel Reinforcement :
 - #3 Deformed Bar (Gr.40) ASTM A-615, Hoops @ 12" o.c.
- Fiber Mesh Reinforcement ASTM C-1116 @ a Rate of 4.0 lbs/cy
- Approximate Assembled Weight :
 - 4' Footing = 600 Lbs
 - 5' Footing = 720 Lbs

NOTES :

MATERIAL :

DOCUMENT APPROVED BY: _____ DATE: _____

DWNG DATE : 06/15/2018

CHKD DATE :

TOLERANCE

MODEL NO.

LOAD BEARING 7000 lbs.

REVISION 1 - DATE

REV

REVISION 2 - DATE



EASTERN PRECAST
COMPANY, INCORPORATED

2 COMMERCE DRIVE, BROOKFIELD, CT 06804
PHONE : (203) 775 - 0230 FAX : (203) 740 - 2059
WWW.EASTERNPRECAST.COM

PRECAST DECK FOOTING